




*Improving the
relationship between
the river and the
road.*

*Stream Restoration and Aquatic Organism
Passage Opportunities During Post Flood
Roadway Repair: An FHWA look at multipurpose
objectives.*

Acknowledgements



- United States Forest Service
- Colorado Department of Transportation
- Colorado Water Conservation Board
- Wildland Hydrology
- Crane Associates
- Round River Design

Agenda

- Who is this guy?
- What do highways have to do with river restoration?
- Stability in Rivers
- Natural Channel Design
- Aquatic Organism Passage
- Bioengineering and Large Woody Debris
- A look at FHWA work on:
 - U.S. Hwy 36
 - County Road 47
 - County Road 43 and
 - Sage Creek Road

Federal Lands Highway Division Offices

Central Federal
Lands Highway
Division (CFLHD)

Serves 14 central,
western, and
southwestern
states & Pacific
Territories



<https://flh.fhwa.dot.gov/>



Stability

Lane's Balance:

An understanding that a stable river carries water, sediment and debris, even during high water, without drastic changes occurring in the depth, width, length, or slope of the channel.





Image Source: Lane, E.W. 1955.

Channel Evolution Process

The adverse consequences of:

- accelerated sediment supply,
- accelerated bank erosion rates,
- degradation,
- aggradation from channel disturbance,
- Stream flow changes,
- sediment budget changes and
- many other causes can lead to channel change.


Image Source: Schumm Model





*A River
out of
balance*

Working with the river...



Understand the natural stable tendencies of rivers can accelerate the recovery processes

Stream width is a function of:

- streamflow occurrence and magnitude
- size and type of transported sediment
- bed and bank materials of the channel

A channel can have a stable width even though the stream is migrating laterally at a constant annual rate

Stream channel morphology is often described in terms of a width/depth ratio related to the bankfull stage cross-section

Make channels deep and flat for flood conveyance!



The Trapezoidal Channel Design


Issues:

- Over-widened, one size fits all design
- Interrupts typical stream processes
- Water Temperature
- Habitat Loss
- ETC.



Riparian Zone:

- Multi-Stage Channel Design.
- Multi-Objective Approach.
- CHANNEL COMPLEXITY!!!



Low Flow Channel

Bankfull Channel

Floodplain and Riparian Zone

Wetlands

Naturally Reinforced Streambank Bioengineering Options

Riprap Road Embankment

Advantages of the multiple stage channel

1. Vegetation establishment on the banks in different zones due to favorable soil moisture
2. Streambank erosion rates are decreased and rooting depth and density are increased
3. Near-bank stress is reduced because the flows are spread-out onto the next highest level
4. During drought, the low flow channel provides sufficient depth for fish habitat
5. During high flows, the low flow channel maintains the sediment transport capacity

Advantages of the multiple stage channel

6. Increases in the magnitude and frequency of flood peaks can be dispersed out of channel and onto a floodplain or flood-prone area
7. Recreational activities and trails can be created on the floodplain and flood-prone area
8. A more natural, visually pleasing river setting
9. A decrease in flood stages for the same magnitude flood due to improved hydraulic and sediment transport efficiency
10. Improved habitat and ecological diversity

Aquatic Organism Passage


- FHWA
- HEC 26:
*Culvert Design
for Aquatic
Organism
Passage.*

Chapter	Description
2 Fish Biology	Fish biological abilities and requirements for successful movement.
3 Culverts as Barriers	Details the types of barriers presented by culverts that were not designed with a fish's biological capacities in mind.
4 Inventory/Assessment/Prioritization	Importance of the hydraulic assessment, inventory and prioritization of road stream crossing projects. Includes a discussion of commonly used techniques, as well as synthesis and recommendations for future prioritization
5 Hydrology	Discussion and comparison of hydrology used in the design of culverts for fish passage. Available techniques and recommended methods are included.
6 Design	Necessary considerations for the design or retrofit of a new or existing roadway-stream crossing installation.
7 Current Design Procedures	Details the current state of fish passage design, including design scenarios from across the country. Covers new installations, culvert replacements, and retrofits.
8 Case Studies/Design Examples	Case studies and/or basic examples of culvert design, installation and retrofit have been included to clarify the design process.
9 Construction/Maintenance	Common scenarios and recommendations for culvert construction and maintenance.
10 Monitoring	Suggested monitoring considerations to ensure long term success of culvert installations, replacements or retrofits.
11 Future Research Needs	Recommendations based on literature review and perceived gaps in current knowledge.

Aquatic Organism Passage Passage Assessment Process

NATIONAL INVENTORY AND ASSESSMENT PROCEDURE : For Identifying Barriers to Aquatic Organism Passage at Road-Stream Crossings


United States Department of Agriculture Forest Service
National Technology and Development Program
7700—Transportation Management
November 2005F; Figure V-1.



Bioengineered Streambanks

- The Stream bank is not a rigid structure to be built in place, but a dynamic system that is naturally resilient.
- Plant roots stabilize the soil while streambank vegetation provides wildlife habitat and helps to dissipate flood velocities.
- Bioengineering techniques include placing logs and root wads in strategic locations, rapid establishment of shrubs in the active channel through live branch layering, and bank protection and floodplain wetland restoration with specially selected plantings and native seed mixes.

Riparian Functions




Bioengineered Techniques

- Rootwad Installation
- Brush/Tree Revetment
- Post Plantings
- Fiberschines
- Brush Trench
- Brush Mattress
- Brush Layer
- Vertical Bundles
- Living Cribwalls
- Brush Layering
- Engineered Log Jams
- Etc!!!


ROOT WAD WITH FOOTER: SECTION

(Not to scale)




ROOT WAD WITH FOOTER: PLAN VIEW

(Not to scale)




TREE REVETMENT: SECTION VIEW

(Not to scale)




BRUSH LAYERING: FILL METHOD

(Not to scale)




LIVE STAKES

(Not to scale)



LIVE POSTS

(Not to scale)



Woody Debris has a Multitude of Benefits

- *Bank Stabilization*
- *Aquatic Habitat*
- *Energy Dissipation*



Too Much Woody Debris?



Bank and Channel Complexity Reduces Velocities & Erosion



Rip Rap Reduces Complexity and Opportunities for Riparian Vegetation



Reinforced Streambanks




- Prior to roadway construction rivers and streams generally meandered back and forth along smooth, sinuous paths, the width of these meanders varying primarily due to valley slope.
- However, when man-made structures such as bridges and culverts are placed along stream channels, this natural pattern is interrupted as the streams are forced to flow around tight bends or through narrow constrictions. In cases like this, protecting the roadway embankment through solely natural channel design can be a tough sell...

Structure Design and Replacement

Benefits:

- Accounts for Natural Channel Conditions
- Removes Unnecessary Channel Constrictions
- Promotes Riparian Connectivity
- Accommodates Aquatic and Terrestrial Passage Through Crossing.




Project Highlights

- Colorado Flood Recovery (Large AOP and River Restoration)
 - US Highway 36 from Lyons to Estes Park
 - County Road 47
 - Larimer County Road 43
- Wyoming Sage Creek Project (Small Scale AOP)
 - Big Sandstone Creek
 - Little Sandstone Creek


A Watershed



+ Large Drainage Area:
Approx. 138,186 acres



Excessive Rainfall




Colorado Flood Event, 9-16 September 2013
Annual Exceedance Probabilities (AEPs) for Worst Case 24-hour Rainfall

Hydrometeorological Design Studies Center
 Office of Hydrologic Development, National Weather Service
 National Oceanic and Atmospheric Administration

<http://www.nws.noaa.gov/ohd/hdsc/>

Created 17 September 2013
 Precipitation frequency estimates are from NOAA Atlas 14, Volume 8, Version 2.
 Rainfall values come from 6-hour multi-sensor data.

- > 1/10
- 1/50 - 1/10
- 1/100 - 1/50
- 1/200 - 1/100
- 1/500 - 1/200
- 1/1000 - 1/500
- < 1/1000



Colorado Flood Event, 9-16 September 2013
Annual Exceedance Probabilities (AEPs) for Worst Case 7-day Rainfall

Hydrometeorological Design Studies Center
 Office of Hydrologic Development, National Weather Service
 National Oceanic and Atmospheric Administration

<http://www.nws.noaa.gov/ohd/hdsc/>

Created 24 September 2013
 Precipitation frequency estimates are from NOAA Atlas 14, Volume 8, Version 2.
 Rainfall values come from 6-hour multi-sensor data.

- > 1/10
- 1/50 - 1/10
- 1/100 - 1/50
- 1/200 - 1/100
- 1/500 - 1/200
- 1/1000 - 1/500
- < 1/1000




U.S. Highway 36

- An ambitious goal!
 - Redesign and Build 2.5 miles of US 36 for flood resilience while improving stream function and maintaining traffic to flood impacted communities.
 - In a six month period over 200,000 cubic yards of rock excavation and blasting, roadway armorment, stream restoration, drainage improvements, and roadway structural section were completed.
- Construction Estimates:
 - 50 Million Dollars
 - 24-48 Months to complete
- Actuals:
 - 20 Million Dollars
 - 9 Months

Embankment Armoring

- We can protect the road and improve floodplain and river function!



Where the River Meets the Road

Along stretches of North St. Vrain Creek and the Little Thompson River, the cooperative U.S. Highway 36 project is shifting the road away from the streams into blasted canyon walls and bioengineering tiered river channels to accommodate varying flow levels—each with improved connection to the floodplain. The goal? A better road, healthier streams and a more resilient system.

Banks constructed to facilitate debris and sediment capture in order to promote plant growth

Root wad bank stabilization

100-YEAR FLOW

BANKFULL FLOW
(Average runoff)

BASE FLOW
EXISTING CHANNEL BOTTOM

5'

Geotextile barrier

Non-grouted riprap filter
Grouted riprap: Keyed into bedrock and filled with soil to promote plant growth

36'

Road surface
Roadbed


10'

Rock fall safety ditch


EXISTING GROUND

BEDROCK

Riprap: Rock or other material used to armor a streambank or streambed from scour and erosion



U.S. Highway 36



Project: CO ER U.S. 36 Repair and Reconstruction

Legend:

- | | | | |
|--------------------|---------------------|---------------------------|------------------------------|
| MILEPOINTS | Construction Limits | Boulder Parcel Boundaries | 17950_sites (Historic Sites) |
| US36 Project Sites | Toe of Fill | Larimer Parcel Boundaries | |
| Centerline | Transition | STREAMS | |
| Edge of Pavement | Top of Cut | LOCAL_ROADS | |




Figure 2:
Site 3-5 Pre and Post Comparison

Date: December 2013

Boulder County, CO

Approximate Roadway Location.
Subject to change.


U.S. Hwy 36; Saint Vrain River Post Flood




U.S. Hwy 36; Little Thompson River Post Flood-2013



County Road 47



County Road 47



County Road 47



Important Lessons from U.S. Hwy 36 and County Road 47

- Recovery actions typically follow a rapid schedule. (Strike while the iron is hot mentality)
- Without watershed master plans; long-term goals for river restoration can be hard to identify quickly.
- Identify restoration opportunities that coincide with repairs to maximize efficiency.
- Traffic Control can be difficult. Sections of roadway were left over widened so that traffic could be accommodated. These areas could receive additional restoration at a later date.
- Collaborate, collaborate, collaborate... Many people will be involved throughout process. Establish mutual goals and understand that not all conversations go as smoothly as you would like.

Larimer County Road 43

Another ambitious goal!

- Redesign and Rebuild a majority of Larimer County Road 43 for flood resilience while improving stream function and maintaining traffic to flood impacted communities **with 1 hour delays and allowable longer closures.**

Project length of 10 miles

- 5 miles of complete reconstruction
- 3.5 miles of heavy reconstruction
- 1.5 miles of spot repair and surfacing (overlay)

Major Scopes of Work

- Earthwork, rock excavation and blasting (250,000 CY)
- Bridge construction (11 bridges)
- Riprap armorment construction (50,000 CY, from onsite generated rock)
- Drainage
- Hot Asphalt Concrete Pavement (30,000 tons)
- Stream Restoration


Construction Estimates:

- 100 Million Dollars
- 3-5 Years to complete

Actuals:


- 50 Million Dollars
- 2 Years

Larimer County Road 43




River Crossing Concepts

- Multi-stage channel through crossing.
- Floodplain reconnection




Numerous River Crossing...



Project: CO Emergency Relief Larimer County Road 43 Repair and Reconstruction

- | | | |
|--|-------------------------------|--------------------------------|
| ● River Crossings (post-flood) | ▭ West Creek (OHWM Pre Flood) | ▬ Toe of Fill |
| ■ River Crossings (pre-flood) | ▭ Tributary | ▬ Transition |
| ▭ Roadway Fill (Pre-Flood) | ▭ River Restoration Area | ▬ Top of Cut |
| ▭ WUS Impacts | ▭ Staging_Stockpile Area | ▬ Alternative River Centerline |
| ▭ North Fork Big Thompson (OHWM Pre Flood) | ▭ Centerline | ▬ Non-FS Land |
| ▭ Miller Fork (OHWM) | ▬ Edge of Pavement | ▭ US Forest Service Owned Land |
| ▭ Devil's Gulch (OHWM) | ▬ Construction Limits | |



Background Imagery:
SINCGRAPH Aerial Maps
(c) 2010 Microsoft Corporation and its data suppliers

Figure 6:
County Road 43:
Waters of the U.S. Assessment


Date: July 2014

Larimer County, CO



Federal Highway Administration
Central Federal Lands
Highway Division


Bridge 3



Notes:
 -River Restoration Areas are conceptual. Detailed plans will be submitted in separate application.
 -NWP 14: Proposed Fill totals 18,589 Square Feet (0.43 Acre)
 -Box Culvert 1 would be removed: 1,285 square feet (0.029 acre)

Project: CO Emergency Relief Larimer County Road 43 Repair and Reconstruction

- | | | |
|--|-------------------------------|--------------------------------|
| ● River Crossings (post-flood) | ▭ West Creek (OHWM Pre Flood) | ▬ Toe of Fill |
| ■ River Crossings (pre-flood) | ▭ Tributary | ▬ Transition |
| ▭ Roadway Fill (Pre-Flood) | ▭ River Restoration Area | ▬ Top of Cut |
| ▭ WUS Impacts | ▭ Staging_Stockpile Area | ▬ Alternative River Centerline |
| ▭ North Fork Big Thompson (OHWM Pre Flood) | ▭ Centerline | ▬ Non-FS Land |
| ▭ Miller Fork (OHWM) | ▭ Edge of Pavement | ▭ US Forest Service Owned Land |
| ▭ Devil's Gulch (OHWM) | ▭ Construction Limits | |



Background Imagery:
 SINC Aerial Maps
 (c) 2010 Microsoft Corporation and its data suppliers

Figure 6:
 County Road 43:
 Waters of the U.S. Assessment

Date: July 2014
 Larimer County, CO



Federal Highway Administration
 Central Federal Lands
 Highway Division


LCR 43 Post Flood Bridge 3



LCR 43 Post Flood Bridge 3




LCR 43 Post Flood Bridge 4



Notes:
 -River Restoration Areas are conceptual. Detailed plans will be submitted in separate application.
 -NWP 14: Proposed Fill totals 18,589 Square Feet (0.43 Acre)
 -Box Culvert 1 would be removed: 1,285 square feet (0.029 acre)

Project: CO Emergency Relief Larimer County Road 43 Repair and Reconstruction

- | | | |
|--|-------------------------------|--------------------------------|
| ● River Crossings (post-flood) | ▭ West Creek (OHWM Pre Flood) | ▬ Toe of Fill |
| ■ River Crossings (pre-flood) | ▭ Tributary | ▬ Transition |
| ▭ Roadway Fill (Pre-Flood) | ▭ River Restoration Area | ▬ Top of Cut |
| ▭ WUS Impacts | ▭ Staging_Stockpile Area | ▬ Alternative River Centerline |
| ▭ North Fork Big Thompson (OHWM Pre Flood) | ▭ Centerline | ▬ Non-FS Land |
| ▭ Miller Fork (OHWM) | ▬ Edge of Pavement | ▭ US Forest Service Owned Land |
| ▭ Devil's Gulch (OHWM) | ▬ Construction Limits | |



Background Imagery:
 SINC Aerial Maps
 (c) 2010 Microsoft Corporation and its data suppliers

Figure 6:
 County Road 43:
 Waters of the U.S. Assessment

Date: July 2014

Larimer County, CO



Federal Highway Administration
 Central Federal Lands
 Highway Division

LCR 43 Post Flood Bridge 4



LCR 43 Post Flood Bridge 4



LCR 43 Post Flood Bridge 4



LCR 43 Post Flood Bridge 4



LCR 43 Post Flood Bridge 4




LCR 43 Post Flood-2016

Bridge 4 –Bioengineering and AOP



LCR 43 Box Culvert



LCR 43 Box Culvert



LCR 43 Post Flood-2016 Road and River Flip Flop




LCR 43 Embankment Armoring



Wyoming Sage Creek Project Big Sandstone Creek

SAGE CREEK ROAD – BIG SANDSTONE STREAM CROSSING STA. 3370+69.21 DETAIL A – PLAN VIEW




NOTE: - TABLE 1 - ROCK GRADATION AND CROSS SECTIONS B, C, D & E ARE ILLUSTRATED ON THE FOLLOWING SHEETS
- DESIGN IN PIPE BASED ON ASSUMED PIPE LENGTH OF 90'

SHEET 1 OF 3


Big Sandstone Creek

SAGE CREEK ROAD – BIG SANDSTONE STREAM CROSSING
 STA. 3370+69.21
 NTS




CROSS SECTION B
 PROFILE VIEW
 NTS

WEIR CROSS SECTION AT INLET/OUTLET OF PIPE
 (PIPE AND FILL SLOPE DELETED FOR CLARITY)




EMBED 24"-36" ANGULAR RIPRAP TO A MINIMUM OF 30" BELOW PROPOSED STREAMBED. EXTEND 24"-36" ANGULAR RIPRAP 6" ABOVE PROPOSED STREAMBED ELEV. SEE DETAIL BELOW

CROSS SECTION C
 UPSTRM/DWNSTRM
 DETAIL AND PROFILE
 NTS



Big Sandstone Creek

SAGE CREEK ROAD – BIG SANDSTONE STREAM CROSSING STA. 3370+69.21 NTS




CROSS SECTION D
RIFFLE DETAIL
NTS

TABLE 1
ROCK GRADATION FOR NATIVE
STREAMBED CHANNEL MATERIAL

PARTICLE SIZE	% VOLUME
< 8 mm	10%
9-64 mm	25%
65-128 mm	50%
129-362 mm	15%

KEY PIECES – Angular Rock having 24" Cubic Dimension



CROSS SECTION E
POOL DETAIL
NTS

PLACED FILLER MATERIAL



FILL ALL VOIDS BETWEEN INDIVIDUAL STREAMBED-SIMULATION ROCKS AND ALL VOIDS LEFT DURING PLACEMENT OF CHANNEL ROCKS AND STREAMBED-SIMULATION ROCK ADJACENT TO FOOTINGS, CONCRETE STRUCTURES, OR CORRUGATED PIPES WITH SELECT BORROW AS SPECIFIED IN FP-03 SUBSECTION 704.07. USE WATER PRESSURE, METAL TAMPING RODS, AND SIMILAR HAND-OPERATED EQUIPMENT TO FORCE MATERIAL INTO ALL SURFACE AND SUBSURFACE VOIDS BETWEEN THE STRUCTURE AND ROCKS AND BETWEEN INDIVIDUAL ROCKS. FILL SHALL EXTEND TO 100 PERCENT OF THE ROCKS' HEIGHT BETWEEN LAYERS AND 50 PERCENT OF THEIR HEIGHT ON THE BED SURFACE OR AS SHOWN ON THE DRAWINGS.

Big Sandstone Creek



Little Sandstone Creek

SAGE CREEK ROAD
LITTLE SANDSTONE STREAM CROSSING



Little Sandstone Creek



Key Benefits of these concepts

- Reduce maintenance costs.
- Reduce societal impacts of road closures.
- Reduce or replace rip-rap with rough woody structures and other bioengineered designs that enhance aquatic habitat.
- Reduce frequency of habitat impacts to aquatic habitat from repetitive repairs infrastructure.

Questions

???

References.

- USDA Forest Service, National Inventory and Assessment Procedure, 2005.
- http://www.r5.fs.fed.us/restoration/Aquatic_Organism_Passage/guidance.shtml
- <http://www.stream.fs.fed.us/fishxing/index.html>

Acknowledgements

- Dave Rosgen and Wildland Hydrology
<http://wildlandhydrology.com/>
- Jeff Crane of Crane Associates
<http://craneassociates.net/>
- Mike Blazewitz of Round River Design
<http://roundriverdesign.com/>